MOBILE TREE COMMISSION

September 21, 2021

MTC-082464-2021

55 Batre Lane

Clear Trees in Right-of-Way to allow development of the property.

Council District 7

Applicant: Aubrey Bishop

Property Owner: Aubrey and Breanne Bishop, IV

Historic District: Not applicable

Tree Location(s): Right-of-way along Batre Lane

Species and Size: Trees in ROW

• 17in magnolia

- 2 ~6in magnolia (volunteers under the 17in tree)
- 1 multi-trunk camphor 8in (largest leader)
- 1 6in water oak
- 1 12in magnolia
- 1 6in magnolia (volunteers under the 6in tree)
- 1 5in water oak

Reason for removal:


To allow development of the property (current vacant and undeveloped).

Urban Forestry Comments:

Removal request recommended for approval.

Recommendation:

Urban Forestry recommends Approval.





Agenda #2: 55 Batre Lane



Agenda #2: 55 Batre Lane

Mobile Tree Commission





<u>5</u>0

100

Feet 200 Mobile Tree Commission








CITY OF MOBILE RIGHT OF WAY NOTES:

- ALL WORK WITHIN THE CITY OF MOBILE RIGHT OF WAY MUST COMPLY WITH THE "MOBILE RIGHTS OF WAY CONSTRUCTION AND ADMINISTRATION ORDINANCE". A COPY OF THE ORDINANCE MAY BE FOUND AT http://cityofmobile.org, ONLINE SERVICES, FORMS AND APPLICATIONS, ENGINEERING, RIGHTS OF WAY CONSTRUCTION AND ADMINISTRATION ORDINANCE.
- ALL WORK SHALL BE IN COMPLIANCE WITH THE STORM WATER DRAINAGE ORDINANCE AND FLOOD PLAIN MANAGEMENT PLAN OF THE CITY OF MOBILE, ALABAMA, INCLUDING BUT NOT LIMITED TO:
- 4. a. DO NOT ALTER THE NATURAL DRAINAGE FLOW PATTERN IN THE AREA OF WORK.
 4.b. DO NOT DIVERT STORM WATER ONTO ADJACENT PROPERTY OR INCREASE THE AMOUNT OF NATURAL DRAINAGE FLOW ONTO ADJACENT PROPERTY OWNER OR PREVENT THE NATURAL FLOW OF WATER IN THE AREA OF WORK.
- DO NOT FILL WETLANDS WITHOUT A PERMIT FROM THE US ARMY CORPS OF ENGINEERS. ANY WORK IN THE FLOOD PLAIN IS IN COMPLIANCE WITH ALL THE REQUIREMENTS OF DIVISION2, FLOOD PLAIN REQUIREMENTS OF CITY OF MOBILE, ALABAMA STORM WATER DRAINAGE ORDINANCE.
- ANY DAMAGE TO ANY CITY OF MOBILE FACILITY OR DRAINAGE STRUCTURE, DITCH, ETC. SHALL BE THE RESPONSIBILITY OF THE PERMITTEE TO
- NOTIFY THE CITY OF MOBILE IMMEDIATELY IF ANY DAMAGE OCCURS. JESSE YAWN SHOULD BE NOTIFIED AT (251) 208-7145 IN THE CITY OF MOBILE RIGHT OF WAY DEPARTMENT.
- ANY EXCESS SOIL FROM A HAND HOLE OR ANY EXCAVATION FOR PITS, ETC., SHALL BE REMOVED FROM THE RIGHT OF WAY (NOT LEFT IN THE RIGHT OF WAY).
 THE INSTALLATION OF AN IRRIGATION SYSTEM WITHIN THE CITY OF MOBILE RIGHT OF WAY WILL REQUIRE THE APPROVAL OF AN IRRIGATION PLAN AND A CITY OF MOBILE RIGHT OF WAY PERMIT.
 ALL DISTURBED AREAS OF THE RIGHT OF WAY TO BE SOLID SODDED AND EXISTING BARE AREAS MAY REQUIRE SOD. EXISTING VEGETATION MAY REQUIRE REMOVAL AND PLACEMENT OF SOD DEPENDING ON ITS CONDITION. THE SOD IS REQUIRED TO BE INSTALLED FLUSH WITH
- O. ALL STORM DRAIN PIPE INSTALLED IN THE CITY OF MOBILE RIGHT OF WAY, CITY OF MOBILE EASEMENT, OR CARRYING PUBLIC STORMWATER ARE TO HAVE THE JOINTS WRAPPED WITH FILTER FABRIC, ARE REQUIRED NOT TO HAVE ANY LIFTING HOLES (FILLING THE LIFTING HOLES IS NOT ALLOWED), SHALL BE A MINIMUM OF 15 INCH IN DIAMETER, AND SHALL BE REINFORCED CONCRETE PIPE (RCP). THE CONTRACTOR NEEDS TO NOTIFY THE PIPE MANUFACTURER AHEAD OF TIME THAT THE PROJECT IS WITHIN THE CITY OF MOBILE RIGHT OF WAY.
- . THE CITY OF MOBILE REQUIRES A MINIMUM OF THIRTY-SIX INCH SEPARATION BETWEEN ANY PIPE/STRUCTURE AND A CITY OF MOBILE STORM DRAINPIPE. PROVIDE A CROSS-SECTION RELATIVE TO ALL PROPOSED PIPE INSTALLATIONS THAT ARE ADJACENT TO A STORM DRAINPIPE(S) WITHIN THE CITY OF MOBILE RIGHT OF WAY. THE CROSS-SECTION WILL NOT BE REQUIRED IF THE PIPE IS INSTALLED BY A UTILITY COMPANY AND NOT THE PROJECT'S CONTRACTOR. 12. ALL SIDEWALK CONSTRUCTION MUST COMPLY WITH CITY OF MOBILE CITY ENGINEERING STANDARD DRAWING 12, "CONCRETE SIDEWALK DETAILS". REFER TO THE STANDARD DRAWING DETAILS INCLUDED IN THE PLAN.
- ULTIMATELY THE DECISION OF THE CITY. 4. AN ADA COMPLIANT TRUNCATED DOME PANEL WILL BE REQUIRED ON THE SIDEWALK AT EACH SIDE OF THE DRIVEWAY. THE TRUNCATED DOME PANEL MUST BE A POLYMER COMPOSITE TRUNCATED DOME PANEL THAT MEETS THE REQUIREMENTS STATED IN THE CITY ENGINEERING TYPICAL HANDICAP CURB RAMP STANDARD DRAWING SEVEN.

13. ANY SIDEWALK PANELS WHICH ARE CRACKED, HAVE BEEN SHOVED CREATING A TRIPPING HAZARD, OR THOSE WHICH HAVE BEEN WORN TO THE EXTENT THAT THEY CREATE A SLIPPING HAZARD, ARE REQUIRED TO BE REPLACED. THE DETERMINATION OF THE CONDITION IS

- 5. THE FINAL RESURFACING LIMITS SHALL BE AT THE DISCRETION OF THE CITY ENGINEER, TO BE DETERMINED AT A FIELD INSPECTION/SITE VISIT UPON COMPLETION OF THE INSTALLATION OF ALL PERMITTED INFRASTREUCTURE/FACILITES, PRIOR TO THE CONTRACTOR BEGINNING
- 16. A VIDEO SHALL BE SUBMITTED TO THE CITY SHOWING THE UNDERGROUND DETENTION SYSTEM PIPES, THE PIPE FROM THE OUTLETS STRUCTURES TO THE CITY DRAINAGE SYSTEM, AND THE PIPE CARRYING PUBLIC WATER. THE PIPE MUST BE VIDEOED AFTER THE PROJECTS COMPLETION, BUT PRIOR TO THE REQUEST FOR A CERTIFICATE OF OCCUPANCY. SUBMIT THE VIDEO TO THE CITY OF MOBILE WITH THE ENGINEER'S AS-BUILT CERTIFICATION PACKAGE. THE VIDEO NEEDS TO BE REVIEWED BY THE PROJECT ENGINEER BEFORE BEING SUBMITTED TO THE CITY. EACH JOINT NEEDS TO BE PANNED LEFT AND RIGHT AS WELL AS ANY DEFICIENCIES BEING WELL DOCUMENTED VIA VIDEOGRAPHY, INCLUDING A WRITTEN REPORT.
- 7. PROVIDE THE LENGTH OF THE ALL PROPOSED FIBER OPTIC CABLE, COAXIAL CABLE, CONDUIT, STORM DRAINPIPE, WATER LINE, SANITARY SEWER LINE, DUCT BANKS, POWER LINES, AND/OR ANY ADDITIONAL BORING, TRENCHING, OR EXCAVATION ACTIVITIES WITHIN THE CITY OF MOBILE RIGHT OF WAY. IF THE CONSTRUCTION INVOLVES OPEN CUTS TO THE RIGHT OF WAY, PROVIDE THE WIDTH AND DEPTH AND CLEARLY SHOW THE LIMITS ON THE PLANS. 18. IF THE PERMIT HOLDER IS NOT A CURRENT FRANCHISEE WITH THE CITY OF MOBILE, A BOND WILL BE REQUIRED FOR ALL WORK THAT IS PERFORMED WITHIN THE CITY OF MOBILE RIGHT OF WAY. THE BOND AMOUNT SHOULD BE BASED UPON THE TOTAL COST OF THE PROJECT (PORTION WITHIN THE CITY OF MOBILE RIGHT OF WAY).




CITY OF MOBILE EROSION CONTROL NOTES:

- . CITY OF MOBILE 10 DAY RULE APPLIES TO THIS PROJECT. NPDES CONSTRUCTION GENERAL PERMIT, PART III. B, REQUIRES MEASURES TO BE IMPLEMENTED ON ALL AREAS NOT UNDERGOING ACTIVE DISTURBANCE OR ACTIVE CONSTRUCTION AND PROGRESSIVE CONSTRUCTION FOR LONGER THAN 10 DAYS TO PREVENT/MINIMIZE EROSION AND ENSURE TIMELY TEMPORARY VEGETATIVE COVER, AND PERMANENT VEGETATION OR COVER OF ALL DISTURBED AREAS WHEN DISTURBANCE IS COMPLETE.
- 2. ALL DISTURBED AREAS SHALL BE STABILIZED IMMEDIATELY. ALL AREAS WITHIN THE RIGHT OF WAY ARE TO BE SOLID SOD.
- 3. THE CONTRACTOR SHALL TAKE ALL MEASURES TO ENSURE THAT SOD THRIVES AFTER INSTALLATION.
- 4. THIS SITE SHALL COMPLY WITH ALL CITY ORDINANCES, INCLUDING EROSION & SEDIMENTATION CONTROL AND WETLANDS.
- 5. ALL CLEARING AND DEMOLITION DEBRIS, CONSTRUCTION AND DOMESTIC WASTE, AND HAZARDOUS AND TOXIC WASTE SHALL BE HAULED OFF SITE AND PROPERLY DISPOSED OF.
- 6. CONTRACTOR IS REQUIRED TO SUPPLY AND MAINTAIN MEASURES NEEDED TO PROTECT THE EXISTING TREES DURING ALL PHASES OF CONSTRUCTION.
- 7. ALL EROSION CONTROL MEASURES ARE TO BE IN ACCORDANCE WITH THE ALABAMA HANDBOOK FOR EROSION CONTROL, SEDIMENT CONTROL, AND STORM WATER MANAGEMENT ON CONSTRUCTION SITES AND URBAN AREAS (LATEST EDITION), AND SHALL BE MAINTAINED AT ALL TIMES DURING CONSTRUCTION ACTIVITIES.
- B. THE EROSION CONTROL MEASURES SHOWN ARE A REQUIRED MINIMUM. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PREVENTION OF SEDIMENT TRANSPORT FROM THIS PROPERTY IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REGULATIONS DURING CONSTRUCTION. THE CONTRACTOR SHALL INSTALL ADDITIONAL DEVICES AND IMPLEMENT ADDITIONAL PRACTICES IF WARRANTED BY FIELD
- 9. THE CONTRACTOR'S SITE SUPERINTENDENT SHALL INSPECT AND MAINTAIN ALL EROSION CONTROL DEVICES AND PRACTICES DAILY.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL EROSION CONTROL MEASURES EXCEPT CHANNEL LINING AND OUTLET PROTECTION AFTER SITE STABILIZATION. THE CONTRACTOR SHALL DRESS ALL AREAS TO THE LINE AND GRADE SHOWN ON THESE PLANS.
- 11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING AND/OR FLUSHING SEDIMENT FROM EXISTING STORM DRAINS IF AN EXCESSIVE AMOUNT IS COLLECTED DURING CONSTRUCTION ACTIVITIES.
- 12. REMOVE ACCUMULATED SEDIMENT WHEN DEPTH REACHES 1/4 OF THE HEIGHT OF BARRIER.
- 13. THE CONTRACTOR IS REQUIRED TO MAINTAIN THE STONE IN THE CONSTRUCTION ENTRANCE THROUGHOUT CONSTRUCTION THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY TRACKING OR SEDIMENT LEAVING THE SITE.

GINEERING, & MAY NOT BE REPRODU WITHOUT WRITTEN PERMISSION SISHO P SH W W R: C2107-005 JOC AUGUST 2021 SUE DATE: ★ PROFESSIONAL ** 7/6/2018 SHEET TITLE & NUMBER: SITE PLAN

HESE DRAWINGS & DESIGN INTENT AF THE SOLE PROPERTY OF BETHEL



THESE DRAWINGS & DESIGN INTENT AR THE SOLE PROPERTY OF BETHEL ENGINEERING, & MAY NOT BE REPRODUC WITHOUT WRITTEN PERMISSION.

Executive Park Cir 10bile, AL 36606 251-661-4747

bethel Engineering

DETAILS

------------DESCRIPTION

JECT NUMBER: C2107-005
WN BY: JOC

CHECKED BY: VDL
SSUE DATE: AUGUST 202

ABAMANA NO 24712

PROFESSIONAL TO THE PROFESSI

SHEET TITLE & NUMBER:

DETAILS

2