18 & 19

PLANNED UNIT DEVELOPMENT

& SUBDIVISION STAFF REPORT Date: May 7, 2009

DEVELOPMENT NAME Josephine Allen Subdivision

SUBDIVISION NAME Josephine Allen Subdivision

LOCATION Area bounded by Dr. Thomas Avenue North, Herman

Drive, extending to the South side of Chin Street

CITY COUNCIL

DISTRICT District 2

AREA OF PROPERTY 3 Lots / $43.8 \pm acres$

<u>CONTEMPLATED USE</u> Planned Unit Development Approval to allow multiple buildings on a single building site in a Multi-Family Residential District, and Subdivision approval to create 3 lots.

TIME SCHEDULE

FOR DEVELOPMENT None provided.

ENGINEERING

COMMENTS

Show Minimum FFE on plans and plat. For Lot #1, all buildings will be subject to A Zone restrictions and requirements unless this subdivision application is revised to subdivide out the portion of Lot #1 that is located in the A Zone. No fill is allowed within a special flood hazard area without providing compensation. Must comply with all storm water and flood control ordinances. Any work performed in the right of way will require a right of way permit. Dedication of 5 feet of additional ROW will be required on the portion of Dr. Thomas Avenue N. that has a 40 foot ROW. A minimum of a 25 foot radius to be dedicated to the City of Mobile is required at the SE corner of Lot #1 and the SW corner of Lot #2. A drainage easement will be required for any storm drainage system receiving drainage from a public street. The size and location of any required easements is subject to the approval of the City Engineer.

TRAFFIC ENGINEERING

<u>COMMENTS</u> Driveway number, size, location, and design to be approved by Traffic Engineering and conform to AASHTO standards.

URBAN FORESTRY

COMMENTS Property to be developed in compliance with state and local laws that pertain to tree preservation and protection on both city and private properties (State Act 61-929 and City Code Chapters 57 and 64).

Hold application over until revised site plan can be submitted showing proposed development with three existing Live Oak Trees on site.

FIRE DEPARTMENT

<u>COMMENTS</u> All projects must comply with the requirements of the 2003 International Fire Code, including Appendices B through D, as adopted by the City of Mobile, and the 2003 International Existing Building Code, as appropriate. Specific compliance with Section 508.5.1 – Fire Hydrants, and Appendices C and D – Fire Hydrant Spacing and Access.

REMARKS The applicant is seeking Planned Unit Development Approval to allow multiple buildings on a single building site in a Multi-Family Residential District, and Subdivision approval to create 3 lots. The site is located in Council District 2, and according to the applicant is served by public water and sanitary sewer.

The purpose of this application is to create three legal lots, and to accommodate new development via PUD approval on proposed Lots 1 and 2: a total of 14 dwelling units (7 duplex structures) and a new cultural arts center are proposed. Lots 1 and 2 formerly contained public housing units similar to those on proposed Lot 3, however, the units were demolished between 1997 and 2002. The existing Josephine Allen public housing units on proposed Lot 3 will remain with no changes.

Planned Unit Development review examines the site with regard to its location to ensure that it is generally compatible with neighboring uses; that adequate access is provided without generating excess traffic along minor residential streets in residential districts outside the PUD; and that natural features of the site are taken into consideration. PUD review also examines the design of the development to provide for adequate circulation within the development; to ensure adequate access for emergency vehicles; and to consider and provide for protection from adverse effects of adjacent properties as well as provide protection of adjacent properties from adverse effects from the PUD. PUD approval is site plan specific, thus any changes to the site plan / Subdivision plat will require approval by the Planning Commission.

Subdivision review examines the site with regard to promoting orderly development, protecting general health, safety and welfare, and ensuring that development is correlated with adjacent developments and public utilities and services, and to ensure that the subdivision meets the minimum standards set forth in the Subdivision Regulations for lot size, road frontage, lot configuration, etc.

The existing site is partially developed and zoned R-3, Multi-Family Residential. To the East of the site are businesses located in R-1, Single Family, and I-1, Light Industrial districts. South of the site are residences and businesses located in R-2, Two-Family and I-2, Heavy Industrial districts. West and North of the site are residences in an R-2 district.

The site has frontage onto multiple minor public and private streets. The right-of-way for Dr. Thomas Avenue North (a public street), where it is West of Reddy Street, is below the minimum 50-foot width required by the Subdivision Regulations, thus dedication necessary to provide

sufficient right-of-way will be required. As pointed out in the Engineering comments, corner radii dedications will also be required. All other streets have adequate right-of-ways.

The 14 proposed dwelling units on Lot 1 will be built as duplex structures. Each unit will have a curb-cut onto Dr. Thomas Avenue Drive North. The applicant should ensure adequate off-street parking for 21 vehicles, and the existing parking lot that will remain, located at the corner of Reddy Street and Herman Drive, should result in adequate parking.

As 4 of the proposed dwelling units will be designed to meet Americans with Disabilities Act accessibility requirements, the applicant should ensure that the driveways are of sufficient length to prevent vehicles from overhanging into the right-of-way or public sidewalks. The size, design and location of any new curb-cuts shall be approved by Traffic Engineering and conform with AASHTO standards.

As Lot 1 is zoned R-3, full compliance with the tree and landscape requirements of the Zoning Ordinance will be required, however, the site plan lacks sufficient information for staff to determine if the requirements are fulfilled. Existing trees are not depicted on the site plan, thus Urban Forestry has requested a holdover of the application.

A 9,400 square foot cultural arts center is proposed for Lot 2. A parking lot contain 34 spaces is also proposed, as is a storm water detention facility. If a parking ratio of 1 space for 300 square feet of gross floor area is used, adequate parking will be provided on site. The parking lot will have an entrance onto Dr. Thomas Avenue North and onto Herman Drive (private street). The size, design and location of any new curb-cuts shall be approved by Traffic Engineering and conform with AASHTO standards. Existing on-street parking will remain.

As the cultural arts center site is zoned R-3, full compliance with the tree and landscape requirements of the Zoning Ordinance will be required, however, the site plan lacks sufficient information for staff to determine if the requirements are fulfilled.

New sidewalks are depicted on the PUD site plan where new development is proposed. As the new residences will include accessible units, the applicant should ensure that continuous sidewalks are provided along all public and private street frontages where new development is proposed, and that the existing recreation center and proposed cultural arts center are accessible via sidewalk by the mobility challenged.

Planned Unit Developments require 700 square feet of "common open space" per dwelling unit (per section 64-5.C.2.c. of the Zoning Ordinance), however, the applicant has not indicated the amount of landscape or common area being provided on Lot 1, which contains the new dwelling units. The PUD site plan should be revised to show required common open space information, as well as the required tree and landscape information.

Related to tree compliance, there is no indication as to the presence of overhead power lines. Where overhead powerlines exist, tree selection within 15 feet (measured horizontally) is limited to live oaks for any required overstory tree, and crepe myrtles for any required understory tree.

A note should be placed on the site plan stating this, and any overhead powerlines to remain should be indicated on the site plan.

No dumpster is depicted on the site plan. If the residences or the cultural center site include dumpsters, they must be depicted on the site plan, and must be screened by a 6-foot high wooden privacy fence. If no dumpster will be used, a note should be placed on the site plan explaining how garbage pick-up will be undertaken.

The geographic area defined by the city of Mobile and its planning jurisdiction, including this site, may contain Federally-listed threatened or endangered species as well as protected nongame species. Development of the site must be undertaken in compliance with all local, state and Federal regulations regarding endangered, threatened or otherwise protected species.

It appears that most of the development will occur outside of the floodzones associated with Three Mile Creek and the Mobile River, however the applicant should ensure that development complies with all applicable federal, state and local regulations relating to floodplain development, prior to the issuance of any permits or land disturbance activities.

RECOMMENDATION

Subdivision: The application is recommended for Holdover until the June 4th meeting so that the following can be undertaken, with revisions provided by May 18th:

- 1) Revision to depict compliance with Engineering comments (Show Minimum FFE on plans and plat. For Lot #1, all buildings will be subject to A Zone restrictions and requirements unless this subdivision application is revised to subdivide out the portion of Lot #1 that is located in the A Zone. No fill is allowed within a special flood hazard area without providing compensation. Must comply with all storm water and flood control ordinances. Any work performed in the right of way will require a right of way permit. Dedication of 5 feet of additional ROW will be required on the portion of Dr. Thomas Avenue N. that has a 40 foot ROW. A minimum of a 25 foot radius to be dedicated to the City of Mobile is required at the SE corner of Lot #1 and the SW corner of Lot #2. A drainage easement will be required for any storm drainage system receiving drainage from a public street. The size and location of any required easements is subject to the approval of the City Engineer.); and
- 2) Revision of the plat to reflect new area calculations and setbacks based upon right-of-way dedication.


Planned Unit Development: The application is recommended for Holdover until the June 4th meeting so that the following can be undertaken, with revisions provided by May 18th:


1) Revision to depict compliance with Engineering comments (Show Minimum FFE on plans and plat. For Lot #1, all buildings will be subject to A Zone restrictions and requirements unless this subdivision application is revised to subdivide out the portion of Lot #1 that is located in the A Zone. No fill is allowed within a special flood hazard area without providing compensation. Must comply with all storm water and flood control ordinances. Any work performed in the right of way will require a right of way permit. Dedication of 5 feet of additional ROW will be required on the portion of Dr. Thomas

Avenue N. that has a 40 foot ROW. A minimum of a 25 foot radius to be dedicated to the City of Mobile is required at the SE corner of Lot #1 and the SW corner of Lot #2. A drainage easement will be required for any storm drainage system receiving drainage from a public street. The size and location of any required easements is subject to the approval of the City Engineer.);


- 2) Revision to show existing Live Oak trees on proposed Lot 1, with proposed development;
- 3) Revision to depict compliance with Fire Department comments (All projects must comply with the requirements of the 2003 International Fire Code, including Appendices B through D, as adopted by the City of Mobile, and the 2003 International Existing Building Code, as appropriate. Specific compliance with Section 508.5.1 Fire Hydrants, and Appendices C and D Fire Hydrant Spacing and Access.);
- 4) Revision of the site plan to show full compliance with the tree and landscaping requirements of the Zoning Ordinance for proposed Lots 1 and 2, including calculations for landscape areas and required PUD common open space for development on Lot 1;
- 5) Revision of the site plan to show sidewalks along all public and private street frontages for those lots accommodating new development;
- 6) Revision of the site plan, if necessary, to provide adequate paved off-street parking area to ensure that driveway length leading to garage/carport can accommodate one full-size pick-up or SUV, with no overhang into the right-of-way or required sidewalk;
- 7) Revision of the site plan to depict a screen dumpster, if one will be used, or placement of a note on the site plan explaining how garbage removal is undertaken; and
- 8) Placement of a note on the site plan stating that any tree planted within 15 feet of an overhead powerline shall be either live oak (overstory) or crepe myrtle (understory), and depiction of any overhead powerlines that will remain after redevelopment.

LOCATOR MAP






PLANNING COMMISSION VICINITY MAP - EXISTING ZONING



The site is surrounded by single family residences and other miscellaneous land use.




PLANNING COMMISSION VICINITY MAP - EXISTING ZONING



The site is surrounded by single family residences and other miscellaneous land use.

APPLICATION	NUMBER	18 & 19	_ DATE _	May 7, 2009	N
APPLICANT Josephine Allen Subdivision					\$
REQUEST	Subdivision, Planned Unit Development				
					NTS

SITE PLAN



The site plan illustrates the proposed buildings and parking, setbacks and roads.

APPLICATION	N NUMBER <u>18 & 19</u> DATE <u>May 7, 2009</u>	_ N			
APPLICANT _	Josephine Allen Subdivision				
REQUEST	Subdivision, Planned Unit Development				
		NTS			