18 & 19

PLANNED UNIT DEVELOPMENT

& SUBDIVISION STAFF REPORT Date: December 20, 2007

DEVELOPMENT NAME Perch Creek Preserve

SUBDIVISION NAME Perch Creek Preserve

LOCATION North side of Winston Road, 1100'+ West of Dauphin

Island Parkway, extending West and South to Perch Creek

CITY COUNCIL

DISTRICT District 4

AREA OF PROPERTY 116 Lots / 85.1± Acres

CONTEMPLATED USE Planned Unit Development Approval to allow a gated, 18'-wide, aggregate- surfaced private street single-family residential subdivision with reduced lot widths and sizes, reduced front and side setbacks, and increased site coverage of 50%.

TIME SCHEDULE

FOR DEVELOPMENT None provided.

ENGINEERING

COMMENTS

No fill in AE flood plain without flood study. If no fill proposed, add note to plat stating that the existing contour elevations are not to be changed. Minimum finished floor elevation to be obtained from City Engineering Dept. – to be 1' above high water elevation for Hurricane Katrina in this area. Show minimum finished floor elevation on each lot. It is the responsibility of the applicant to look up the site in the City of Mobile (COM) GIS system and verify if NWI wetlands are depicted on the site. If the COM GIS shows wetlands on the site, it is the responsibility of the applicant to confirm or deny the existence of wetlands on-site. If wetlands are present, they should be depicted on plans and/or plat, and no work/disturbance can be performed without a permit from the Corps of Engineers. Must comply with all storm water and flood control ordinances. Any work performed in the right of way will require a right of way permit.

Flood Study Required for 50 lots or more – or, 5 acres or more?

TRAFFIC ENGINEERING

<u>COMMENTS</u> Driveway number, size, location, and design to be approved by Traffic Engineering and conform to AASHTO standards.

URBAN FORESTRY

COMMENTS Property to be developed in compliance with state and local laws that pertain to tree preservation and protection on both city and private properties (State Act 61-929 and City Code Chapters 57 and 64).

FIRE DEPARTMENT

COMMENTS

Subdivision layout and design must comply with the requirements of the 2003 International Fire Code, including Appendices B through D, as adopted by the City of Mobile. Subdivisions which include new cul-de-sacs longer than 150' must comply with the design requirements of Appendix D of the 2003 International Fire Code. For new cul-de-sacs longer than 750' in length, the location of fire hydrants must be illustrated on the preliminary plat, or an intermediate turn around that complies with Appendix D must be provided. Must comply with Section 503 which states that the minimum width of an apparatus access street is to be 20', and where adjacent to a hydrant the minimum width is to be 26'

REMARKS The applicant is seeking Planned Unit Development Approval to allow a gated, 18'-wide, aggregate- surfaced private street single-family residential subdivision with reduced lot widths and sizes, reduced front and side setbacks, and increased site coverage of 50%., and Subdivision Approval to create 116 Lots on 85.1± Acres. The site is located in Council District 4, and according to the applicant is served by public water and sanitary sewer.

Planned Unit Development review examines the site with regard to its location to ensure that it is generally compatible with neighboring uses; that adequate access is provided without generating excess traffic along minor residential streets in residential districts outside the PUD; and that natural features of the site are taken into consideration. PUD review also examines the design of the development to provide for adequate circulation within the development; to ensure adequate access for emergency vehicles; and to consider and provide for protection from adverse effects of adjacent properties as well as provide protection of adjacent properties from adverse effects from the PUD. PUD approval is site plan specific, thus any changes to the site plan must be approved by the Planning Commission.

Subdivision review examines the site with regard to promoting orderly development, protecting general health, safety and welfare, and ensuring that development is correlated with adjacent developments and public utilities and services, and to ensure that the subdivision meets the minimum standards set forth in the Subdivision Regulations for lot size, road frontage, lot configuration, etc.

The narrative submitted with the applications describes the development as a gated community of 116 lots on 85 acres with not direct wetlands impacts. The narrative goes on to state that two of the most beautiful areas on the site are being set aside for the enjoyment of the residents, along with aces of uplands and wetlands being preserved as common areas with use restrictions. Building lots will have to be approved by an Architectural Review Committee, and tree removal allowed only as needed.

A land use summary provided with the applications states that 58 acres of the 85 acre site will remain as Common Open Space. Of those 58 acres, 38 acres are wetlands and creek, and the remaining 20 acres which are uplands, will include a natural buffer behind each lot and will remain natural with select clearing for nature trails.

The development proposes private streets with a gated entry. The narrative states that the streets are to be 18' with 14' wide surfaces on one-way lanes. Surfaces are proposed to be crushed aggregate permeable paving surface with ribbon curb, and asphalt or pavers to be used at intersections and other areas with heavy turning movements. Driveways are to be permeable.

Lots within the proposed subdivision are to be a minimum of 5500 sq.ft., with a minimum width of 50°. A reduced front setback of 20° is being requested in lieu of proposing a reduced private street right-of-way. Reduced side yard setbacks of 5° and increased site coverage of 50% are also being increased. All so the houses may be clustered to preserve more open space and enable the preservation of more trees on each lot.

The narrative ends with the statement that preservation, open space, natural common areas and privacy combine to create a true Smart Growth Development.

While statements and points made in the narrative may be accurate, there are several issues that must be addressed.

The first is that of studies that should be required before the application is acted upon. Given the number of lots proposed (116), and the facts that the site contains wetlands, is adjacent to a navigable waterway, and the overwhelming majority of the site is located in the AE Flood Zone, a Flood Study should be required. While this requirement is not something that has necessarily be required previously, it is something that COM staff recently learned was needed for COM FEMA compliance.

Another study that may be appropriate given the number of lots is a traffic study. Recently traffic impact of subdivisions has become more and more of an issue. At a recent business meeting the Commission discussed various types of developments and at what threshold would a Traffic Impact Study be required. Numbers for residential subdivisions varied from 50 lots to 150 lots. While no determination was formally made, given the nature of the access to this development as well as the culvert or structure it must cross, there is some concern regarding the adequacy of access. Further, there may be concern by MFD regarding not only the streets (as referenced in MFD comments), but also with regard to the structure's adequacy to accommodate fire apparatus.

The site is adjacent to Perch Creek, a navigable waterway and tributary to Dog River. It appears that the may contains wetlands and is located within the "100 year" and "500 year" floodplains. The presence of wetlands and floodplains on the site indicate that the area may be environmentally sensitive; therefore, the approval of all applicable federal, state and local agencies would be required prior to the issuance of any permits or land disturbance activities. Additionally, the entire Perch Creek Preserve Subdivision (all phases) appear to be located within an area subject to hurricane-related storm surges. The minimum finished floor elevation should be indicated for each lot, and the flood zone(s) should be indicated on the plat.

The geographic area defined by the city of Mobile and its planning jurisdiction, including this site, may contain Federally-listed threatened or endangered species as well as protected non-

game species. Development of the site must be undertaken in compliance with all local, state and Federal regulations regarding endangered, threatened or otherwise protected species.

Another issue is that the development proposes a 50' private street right-of-way, as required by the Subdivision Regulations. However, the streets are proposed to be 18' streets with a ribbon curb (the regulations require two 2' asphalt wings), and 14' one way lanes. The surfacing is proposed to be aggregate, instead of the minimum standard asphalt paving required in the Subdivision Regulations. The issues here relate to MFD requirements, based upon the 2003 International Fire Code (Section 503 which states that the minimum width of an apparatus access street is to be 20', and where adjacent to a hydrant the minimum width is to be 26'), and appendices C & D.

The proposed private streets exceed the maximum length for a cul de sac or closed end street as stated in the Subdivision Regulations, the park areas indicated in the middle of the private street rights-of-ways may be sufficient to allow for a longer cul de sac and allow a fire truck to turn around. However, no information is provided as to the level of clearing and/or improvements there may be in these areas that would address these concerns.

Another issue is that the locations of the one-way and two-way surfaces are not shown on the plan, nor are the areas intended for asphalt or pavers. PUD Approval is site plan specific, therefore the plan should reflect the locations of the one-way and two-way surfaces, and the paving sections.

The plan denotes several areas as "PARK" and others as common area. Neither the narrative nor the plan reference the difference between the two, nor whether the "parks" are to be private or dedicated parks.

RECOMMENDATION

Subdivision: Based upon the preceding, it is recommended that this application be heldover until January 17, 2008 to allow the applicant to:

- 1. submit a Flood Study;
- 2. submit a Traffic Impact Study;
- 3. Revise the plan to comply with the International Fire Code (specifically, but not limited to, Section 503);
- 4. Revise the plat to illustrate locations of one-way and two-way surfacing, and areas of asphalt paving or pavers;
- 5. submit justification for aggregate surfacing in lieu of paved surfacing as required by the Subdivision Regulations;
- 6. Revise the plan to illustrate areas of clearing and/or improvements within the park areas illustrated in the private street rights-of-ways;
- 7. provide information regarding the areas denoted as "Park", explaining the difference between "Park" and "Common Area", and if the "parks" are to be private or dedicated parks;
- 8. provide verification of the adequacy of the culvert/structure on Winston Road to accommodate fire apparatus and the increased traffic generated by the development;


- 9. placement of a note on the plat stating that the approval of all applicable federal, state and local agencies shall be provided prior to the issuance of any permits or land disturbance activities;
- 10. Placement of a note on the plat / site plan stating that approval of all applicable Federal, state and local agencies is required for endangered, threatened or otherwise protected species, if any, prior to the issuance of any permits or land disturbance activities; and
- 11. revision of the plat to reflect minimum finished floor elevation and square footage for each lot.


Planned Unit Development: Based upon the preceding, it is recommended that this application be heldover until January 17, 2008 to allow the applicant to:

- 1) submit a Flood Study;
- 2) submit a Traffic Impact Study;
- 3) Revise the plan to comply with the International Fire Code (specifically, but not limited to, Section 503);
- 4) Revise the plat to illustrate locations of one-way and two-way surfacing, and areas of asphalt paving or pavers;
- 5) submit justification for aggregate surfacing in lieu of paved surfacing as required by the Subdivision Regulations;
- 6) Revise the plan to illustrate areas of clearing and/or improvements within the park areas illustrated in the private street rights-of-ways;
- 7) provide information regarding the areas denoted as "Park", explaining the difference between "Park" and "Common Area", and if the "parks" are to be private or dedicated parks;
- 8) provide verification of the adequacy of the culvert/structure on Winston Road to accommodate fire apparatus and the increased traffic generated by the development;
- 9) placement of a note on the plat stating that the approval of all applicable federal, state and local agencies shall be provided prior to the issuance of any permits or land disturbance activities;
- 10) Placement of a note on the plat / site plan stating that approval of all applicable Federal, state and local agencies is required for endangered, threatened or otherwise protected species, if any, prior to the issuance of any permits or land disturbance activities; and
- 11) revision of the plat to reflect minimum finished floor elevation and square footage for each lot.


All additional information and revised drawing to be submitted by December 27, 2007.

LOCATOR MAP







PLANNING COMMISSION VICINITY MAP - EXISTING ZONING



This site is surrounded by residential land use.



SITE PLAN



This site plan illustrates proposed lot configuration.

APPLICATION	N NUMBER _	18 & 19	DATE _	December 20, 2007	Ņ
APPLICANT -	Perch Creek Preserve Subdivision				Å
REQUEST	STSubdivision, Planned Unit Development				
					NTS